HIGH CREATION INTERIOR	@highcreation @hcinterior @highcreationinterior @hcinterior	18001200532 info@hcinterior.in H-101, LGF, H Block, Sector 63, Noida U.P. 201301402 Office No. 402 & 402A, 4th Floor, JMD Galleria Mall, Badshahpur Sohna Road, Sector-48, Gurugram 122001 www.hcinterior.in

GSTIN : 09AAECH5510R1Z5

Quotation For Mr. Test Lead Digital , Contact Person- Test Lead Digital Subject- Offer for Home Interior Work Dear Sir, Greeting of the day!! This is with reference of your requirement.	**Quote No-** HCIPPL/Quote/25-26/N/100110 **Date-**12-09-2025 **Quotation Valid till** 3 months **Prepared By :** Mr. Nishant Singh **Checked By :**

HIGH CREATION INTERIOR PROJECTS PVT.LTD.

Ground Floor

S.N.	Item Name	Description	Qty	Unit	Price	Total	Remarks
	Wooden Work						
A	**ENTRANCE**						
1	**Shoe Reck (With Sitting Provision)**	1. Carcase Size Upto (3'-0'' X 4'-0''). 2. Shutter with Hydrolic Hinges. 3. 2Nos Drawer System. 4. 1-2 movable or fix shelf. 5. Handle.	1	Nos	27,000	27,000	Carcase:- Century (HDHMR) Shutter:- Century (MDF) External Finish:- Laminate (Virgo / Croma / Dreamlam / Supa) (Century Hardware)
2	**Wooden Panelling**	1. Panelling on Wall with 6-12mm th MDHMR (Cross Bond). 2. finished: laminate. 3. Without Grooving	40	Sqft	570	22,800	
B	**LOUNGE/LIVING / DINING AREA**						

S.N.	Item Name	Description	Qty	Unit	Price	Total	Remarks
1	**T.V. Unit**	1. TV Panel Size (5'-0'' X 6'-0''). 2. 2nos Drawer System in lower unit. 3. Shutter with Hydrolic Hinges. 4. 1-2 movable or fix shelf. 5. Handle. 6. Back site only paneling cove light provision.	1	Sqft	1,220	1,220	Carcase:- Cross Bond (MDHMR) Shutter:- Century (MDF) External Finish:- Laminate (Virgo / Croma / Dreamlam / Supa)
2	**Centre Table**	1. Table Size (3'-0'' x 2'-0'') 2. Table Surface made in MDHMR (Cross Bond)	1	Nos	27,000	27,000	External Finish:- Laminate (Virgo / Croma / Dreamlam / Supa) Top Finish (Glass Top)
3	**Sofa**	1. Leg:- Wooden 2. Foam:- Sleep-lite/Eq. 3. Fabric range upto:- 400- 450/-. 4. Stucture:- Wooden & MDHMR (Cross Bond)	5	Nos	12,500	62,500	
C	**BED ROOM**						
1	**Wardrobe**	1. Carcase Size (6'-0'' X 8'-0''). <span xss=	40	Sqft	1,490	59,600	Carcase:- Cross Bond (MDHMR) Shutter:- Century (MDF) External Finish:- Laminate (Virgo / Croma / Dreamlam / Supa)
2	**Side table (1'-6**	1. Carcase Size (1'-6	2	Nos	10,000	20,000	External Finish:- Laminate (Virgo / Croma / Dreamlam / Supa)
3	**King Size Bed (6'-3**	1. Storage box type. <span xss=	1	Nos	53,000	53,000	External Finish:- Laminate (Virgo / Croma / Dreamlam / Supa)

S.N.	Item Name	Description	Qty	Unit	Price	Total	Remarks
D	**KITCHEN**						
1	**Kitchen**	UPPER CABINATE:- 1. Upper Unit only shutter. 2<span xss=	110	Sqft	2,570	282,700	Carcase:- Century (HDHMR) Shutter (MDHMR) (Hettich Hardware Fittings wire basket) External Finish:- Laminate (Virgo / Croma / Dreamlam / Supa)
					Sub Total:	555,820	
					Discount:	83,373	
					Total:	472,447	
					Final Floor Total:	472,447	

BANK DETAIL FOR PAYMENT:

HIGH CREATION INTERIOR PROJECTS PRIVATE LIMITED

ACCOUNT NO:- 50200067427841 WITH HDFC BANK

IFSC HDFC0001000

Ground Floor Total : 472,447

Site Handling Charges : 0

Grand Total : 472,447

Amount To Be Paid : 0

Notes : Hey Looking forward to doing business with you.

#	Details
1)	GST 18% included as per Govt norms.
2)	Water and Electricity supply will be provided by client.
3)	The entire material viz.; chemicals, tools etc. shall be kept in your safe custody at site, which shall be used on the daily basis by labours. The responsibility of the entire material will be customers if customer resident at the site.
4)	This Project Value is an Estimated Cost based on Information provided by the Client regarding their work requirement. Actual Cost may change once all Designs, Elements & Measurement of Project are finalized.
5)	If there is any change or Addition, then, Unit Price in this Quote Shall be Revised According to Design , Material & Labour Charge.
6)	Final Billing shall be done on actual quantities and measurements. The Same Shall be checked and Certified by both the Parties.
7)	Estimated Cost of Electrical work included, but, it will be charged and billed as per actual work.
8)	The Client or Owner of the Property or Authorised Person as mentioned in Agreement shall take the responsibility in case of a delay in completion deadline due to lack of timely payments as mentioned in the payment schedule.

#	Details
9)	*All material specification as per manufacturing company norms which is selected by Client/designer/Engg etc.
10)	If the project cancellation request received within 48H from order booking then 100% refund of the booking amount. And if cancellation request is received after 48 Hours then HC Interior shall deduct 5% of project value as design or marketing cost. Balance amount shall be refund. (Kindly visit for more details https://hcinterior.in/cancelletion-policy OR kindly visit our website www.hcinterior.in For cancellation policy)
11)	Sqft includes 5% wastage in wooden & modular work.
12)	Site handling charge will be 7% of project value.

(Note:- Item or Work Specification, which is not mentioned In the Quote, will not be supplied by the Company. If, Customer is required to get it done, then, it will be Chargeable basis.

Payment Terms: (Civil + Modular work)	Payment Terms: (Only Modular work)
• 10% advance along with order booking. • 10% after designer visit (handover to design team) • 40% before start of site work • 20% before start of factory work • 20% before dispatch	• 10% advance along with order booking. • 10% after designer visit (handover to design team) • 40% before start of factory work (at the time of validation) • 40% before dispatch

Note:- Payment terms may vary as per scope of work.

Material Specifications:-

HIGH CREATION INTERIOR PROJECTS PVT.LTD.

#	Details
1	**WOOD:-** Crossbond MDHMR (Maximum Density High Moisture Resistant) will be use for whole carcase of all wooden modular & thickness of MDHMR is 16.75 mm with prelam & 16.5mm Century raw MDF will be use in Shutter panel. **Benifits of Crossbond MDHMR:-** 1. No chipping 2. Maximum screw holding strenth 3. Stronger than MDHMR (Cross Bond) wood 4. Density >850kg/m3 **Benifits of Prelam:-** 1. No Bubble of laminate 2. Fade resistance 3. Scretch resistance 4. Easy to clean. (Including cost of all materials, Transportation, cutting and placing to the required size, labour charges, sundries, wastage etc. at all levels complete as per drawings and as per direction of designer-in-Charge). with 10yr warranty*
2	**INTERNAL FINISH:-** Prelam fabric texture.
3	**EXTERNAL FINISH:-** 1mm* thick Laminate (Laminate thickness as per selected folders/brands) will be use on external finish of the wood & edge finished with 1.0 to 1.3 mm thick PVC beeding with internal storage & fixing with L-patty(as per condition), 50mm & 19mm gypsum screw including all Necessary - Fittings are requirment Make:- surface as per design need & designer's selection.(Finish will change acc to client's choice-price may vary acc to material) material costs - Veneer **(Price upto Rs 2000/sheet) Laminates-Price upto Rs 1200. (If laminates were choose from merino, century the difference of sheet price will be pay by the client.** (Thickness of Laminate can be vary as per manufacturer Norms.)
4	**HARDWARES:-** Hardware & fittings as, **Century or Equivalent** (with 10 years warranty).(Handle range upto Rs 350 rs/ pc for 12inches ,8inches-300/rs, 4 inches 150/rs, drawers channels-soft close channels. (if channels will increase the difference will pay by the client's)

#	Details
5	**KITCHEN:-** "**Century or Equivalent**" make will be provided for Chanels, Baskets or hardware. Wire baskets will be provided and max 7 nos of baskets will be provided including grain trolley/ multi-purpose basket/bottle pullout/cup-saucer/bin- basket & GTPT etc. Price of Innotech baskets will be extra. Profile Handles will provided. Max 2 nos of Aluminium Profile shutter provided. Chimney, Hob, geyser & CP fittings will not provided by company.
6	**ELECTRICITY:-** "**KEI/POLYCAB/RR CABEL**" make will be provide for Wiring. 0.75 sqmm to 4 sqmm wire will be provided. Make of Switch/Socket will be "**Anchor-Penta**" (If other brand were choose, difference of price will be pay by the client). If complete wiring not done then mcb will not be provided at the same price.

I accept all term & condition. Please Read term & condition from https://hcinterior.in/term-and-condition, or kindly visit our website www.hcinterior.in for term & condition.

Signature (Client or owner of the Property).----------

HIGH CREATION INTERIOR PROJECTS PVT.LTD.